BRUHAT BANGLORE MAHANAGARA PALIKE

DASARAHALLI-ZONE

DASARAHALLI-SUB-DIVISION.

Name of Work: Providing pot hole Filling of CC roads and De silting of Kempegowda Nagara 5th Cross & Other Cross roads in T.Dasarahalli in Ward No 15 (Emergency Grant)

Estimate Cost :-15.00 Lakhs

BRUHATH BANGALORE MAHANAGARA PALIKE

(7)

Ward 15, Dasarahalli

NAME OF WORK :	**Providing Pot Hole Filling opf CC roads and De-silting of Kempegowda Nagara 5th cross & Other cross roads in T.Dasarahalli in Ward No.15 (Emergency Grant)**
Estimated Cost	**15.00 Lakhs**

Sl.No.	Description of work	Measurments				Qty	Unit	Rate	Amount
		No.s	L	B	D				
1	Earthwork excavation by manual means in Hard Soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 9 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per the direction of Engineer-in-charge of the work..(PWD SR 2016-17, Page No.142, Item No. 19.2)								
	for CC drain	1	1	14.00	2.00	0.95	26.60			
					Total qty.		**26.60**	**cum**	**208.82**	**5555.00**
2	KSRB 4 -1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, including cost of all materials, labour HOM of machinery curing complete as per specifications. Specification No.KBS 4.1, 4.2 (PWD SR 2016-17, Page No.12, Item No. 4.3)								
	for drain	1	1	14.00	2.00	0.15	4.20			
					Total qty.		**4.20**	**sqm**	**5159.02**	**21668.00**
3	KSRRB M2200-5.9. Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008- i) Upto 5 m height. (Pg.No.223, It.no.28.7.9)								
	bottom of drn	1	1	14.00	2.00	0.15	4.20			
	side walls	1	2	14.00	0.20	0.90	5.04			
	for covering	1	1	14.00	2.00	0.20	5.60			
					Total qty.		**14.84**	**sqm**	**6965.26**	**103364.00**
4	KSRRB M2200-6. Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specificationsMORTH Specification No.1600 & 2200 [P. no.17 - I. no.28.8.2]								
	for drains	80kg/cum					1187.20			
	double						***1187.20***	kgs		
					Total qty.		**1.18**	**ton**	**74331.44**	**87711.00**

5	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc,. And removal of form work for **vertical surface** such as walls at any thickness, includig attached pilasters, butresses, plinth cills and string courses cost of all materials, labour complete as per specifications. (Pg. No.15, It. No.4.31)									
	for drain	1	4	14.00		1.00	56.00			
		1	2	16.00		0.20	6.40			
					Total qty.		**62.40**	**sqm**	**310.58**	**19380.00**
6	Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work..(PWD SR 2016-17, Page No.142, Item No. 19.1) including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 5 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per the direction of									
	for CC road									
	5th cross	1	1	145.00	4.20	0.45	274.05			
					Total qty.		**274.05**	**cum**	**175.96**	**48222.00**
7	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications.Page No 149/ Item No. 19.64 PWD SR 2016-17									
		1	1	145.00	4.20		609.00			
					Total qty.		**609.00**	**sqm**	**5.30**	**3228.00**
8	Providing, laying, spreading and compacting stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. Complete as per specifications. MORTH Specification No.406 [P.No.158- It.No20.18]									
		1	1	145.00	4.20	0.20	121.80			
					Total qty.		**121.80**	**cum**	**1768.08**	**215352.00**
9	KSRRB M600-1: Construction of dry lean cement Concrete mix CC1:5:10 with OPC cement @160kgs, with 25mm and down size graded grnite metal coarse aggragate at 0.86cum and fine aggregates @ 0.58cum sub-base over a prepared sub-grade with (Coarse and fine aggregate conforming to IS:383) aggregate cement ratio not to exceed 15:1 Aggregat gradiation after blending to be asper Table 600-1, cement content not to be less than 160kg/cum, optimum moisture content to be determined during trail length construction, concrete strength not to less than 10Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing complete s per specifications(It 22.1 & Page No.176)									
		1	1	145.00	4.20	0.15	91.35			
					Total qty.		**91.35**	**cum**	**3986.66**	**364181.00**

10	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 ReaffirmecF2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. M30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.43cum) ((P.No.177, I.No.22.6.1 of PW,P&IWTD SR 2016-17)									
		1	1	145.00	4.20	0.15	91.35			
					Total qty.		**91.35**	**cum**	**6217.96**	**568011.00**
11	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery,screed vibratory,power Floater,blade and disc etc., with all lead and lift PWD SR 2016-17[P.No.177 -I.No.22.7]									
		1	1	145.00	4.20		609.00			
					Total qty.		**609.00**	**sqm**	**95.40**	**58099.00**
12	Providing groove cutting to concrete pavement for width of 5mm to 10mm and depth 80mm - 100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade, coolant, etc., including cleaning of grove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all amterials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications.(P.No.178, I.No.22.8.1 of PW, P&IWTD SR 2016-17)									
		1	10	4.20			42.00			
					Total qty.		**42.00**	**Rmt**	**121.90**	**5120.00**
									Sub Total	**1499891.00**
									Miscelleneous and rounding off	**109.00**
									Total	**1500000.00**
(Rupees Fifteen Lakhs Only)										

CERTIFICATE

1 *Certified that The work spot has been inspected by me and the work is necessary & site condition*
2 *Certified that the work is not split up*
3 *Certified that the estimate is based on PW,P&IWTD Bangalore Circle SR of 2016-17*
4 *Certified that Adequate & necessary provisions have made in the estimate.*
5 *Certified that the above area comes under BBMP limit*
6 *This Work is not included in any other work taken up*

Asst Engineer
Ward-15

Assistant Executive Engineer
Dasarahalli Sub Division
B.B.M.P

Excecutive Engineer
Dasarahalli Division
B.B.M.P

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-560057

ಸಂ. EE/DD/TS/03/17-18 ದಿನಾಂಕ : 10.7.17

ರೂ. Rs. 15.00/ wchs (Fifteen wchs only)

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಯವ್ಯಯದಲ್ಲಿ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಟಿ.ವಿ.ಎಂ. ಉಪವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ಸಂ. EE/DD/TS/12/17-18 ದಿನಾಂಕ : 10.7.17

ರೂ. Rs. 15.00/ wchs (Fifteen wchs only)

ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಯವ್ಯಯದಲ್ಲಿ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಟಿ.ವಿ.ಎಂ. ಉಪವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು